

**Project:**

Montgomery Point Lock & Dam  
Dewatering Project  
DACW03-97-C-0025

**Location:**

White River, Desha Co.  
Tichnor, AR

**Owner Representative:**

Corps of Engineers,  
Little Rock District  
Mitch Eggburn, P.E.  
35B Wild Goose Lane  
Tichnor, AR 72166  
Ph. 870-850-7106 x102 or 501-324-7192  
Fx. 870-850-6507  
Email: mitchell.t.eggburn@swl02.usace.army.mil

**General Contract / Project Manager:**

J.A. Jones / Atkinson Construction  
P.O. Box 849  
Rosedale, MS 38769

**Subcontract Amount:**

\$2,082,639

**Maintenance Contract Amount:**

\$825,000

**Start & Completion Date:**

Dec-1998 to Oct-2004



**Description of the Project:**

This project provided critical dewatering facilities for the construction of a new Lock & Dam. It also provides power for construction and lighting. We executed the contract on a **Design/Build** basis for review and approval by the COE. The 7 Mega-Watt, 25KV, power distribution system serves 78 well pumps. This system started with a 25KV, Outdoor, Deadfront, **Medium Voltage Switchgear** lineup with automatic power factor correction capacitor banks. This line up feeds 6 power **Unit Substations**, which include a step down transformer to 480 volt and a ATS, Backup 750KW Generator, and 480 Switchboard. These stations are mounted on elevated platforms to get above the 500 year flood level.

# Montgomery Point Lock & Dam Dewatering